

**OFFICE OF THE UNIVERSITY ENGINEER
PATNA UNIVERSITY, PATNA -800 005**

EMERGENT NOTICE INVITING QUOTATION

Quotation No.: 06/2019-20

Date: 24/05/2019

Sealed Quotations are invited in prescribed format for interior decoration work of Vice Chancellor Chamber, Patna University, Patna. For detail terms & conditions, please visit the office of the undersigned on any working days from 10:30 A.M. to 5:00 P.M. or obtain from Patna University website www.patnauniversity.ac.in.

Designation of officer inviting quotation		University Engineer, Patna University, Patna		
Last date of issue/download of Quotation document with Time		Office of The University Engineer Patna University, Patna upto 5:00 pm on 10/06/2019		
Place, Time & Date of receiving of Quotation		Office of the University Engineer, Patna University, Patna upto 3:00 pm on 11/06/2019		
Place, Time & Date of opening Tender		Office of the University Engineer, Patna University, Patna at 3:30 pm on 11/06/2019		
Sr. No.	Name of work	Cost of quotation paper ₹	Required EMD ₹	Completion of Time
1	Part-1 Interior decoration work of Vice Chancellor Chamber, Patna University, Patna (Civil and Electrical work)	2,500/-	5% of quoted amount	Twenty Five Days
2	Part-2 Interior decoration work of Vice Chancellor Chamber, Patna University, Patna (Flooring and Furniture Work)	2,500/-	5% of quoted amount	Twenty Five Days

TERMS & CONDITIONS:

- Paper submitted with quotation:
 - Registration certificate of firm/agency
 - Registration certificate of interior decorator architect
 - Copy of PAN,
 - Copy of GST
 - Copy of 3 Years ITR
 - Experience certificate of similar work.
- Earnest money is to be deposited in the shape of D.D./ Banker's cheque in favour of The University Engineer Patna University, Patna @ 5% of quoted amount (except MSME registered agency).
- Time of Completion: 25 Days
- Payment: (i) 1st running bill 25% of the bid amount as soon as material arrives at site, (ii) 2nd running bill as per the progress of the work, (iii) 3rd and final bill after completion of work.
- The Bidder should inspect the site before filling in and submitting the quotation to get fully acquainted with the scope of work as no claim whatsoever will be entertained for any alleged ignorance thereof. Quotations must be submitted in original and without making any additions, alternations, and as per details given in other clauses given hereunder. The requisite details shall be filled in by the Bidder in the quotation Document wherever required.
- The agency should have experience of similar type of work at any Government organization or Universities.
- The sealed quotation should also be sent through courier/Registered/Speed Post. Conditional quotation or quotations received after the due time and date shall not be entertained in any circumstances. University Authority would not be responsible for any delay or loss of the quotation document, The quotations will be opened in the office of the undersigned in presence of any intending supplier or his/her authorized representative who may wish to be present at the designated time and place. If the fixed date turns out to be the holiday, the date of opening will be the next day.

भ्रष्टाचारी के दबाव में मत रहें, निगरानी विभाग से मिलकर कहें

8. The quotation document can also be downloaded from the website www.patnauniversity.ac.in from intending quotationer and will be submitted with cost of document in the form of Demand Draft in favor of University Engineer. Quotation submitted without cost of quotation document in the form of demand draft will be summarily rejected and the last date for downloading the quotation document from the website is one day prior to the last day of receipt of quotation. Accordingly the draft towards the tender fee shall be dated one day prior to the last date of receipt of quotation.
9. At the time of opening of quotation only participant quotationer or his single authorized representative with authority letter will be allowed to present.
10. The EMD shall be forfeited If the bidder withdraws his bid during the period of bid validity.
11. All disputes, what so ever shall be referred to the sole arbitration of The University Engineer Patna University, Patna and his decision shall be final and binding on the agency.
12. All the matters subject to the jurisdiction of Patna High Court.
13. **Bidders should submit details in the format given at Annexure-1 and should quote the rates in the format given at Annexure-2. Incomplete bids will summarily be rejected. All corrections and alterations in the entries of quotation document will be signed in full by the Bidder with date. No erasing or over- writings are permissible.**
14. The details may also be seen at website www.patnauniversity.ac.
15. **The undersigned reserve** the right to accept or reject any or all the quotation without assigning any reasons.

Sd/-
University Engineer
Patna University, Patna

Memo No.:102/UE

Date:24/05/2019

Copy to:

1. Pro Vice-Chancellor, Patna University, Patna, 3. Financial Advisor, Patna University, Patna, 4. Development Officer cum Coordinator NAAC, Patna University, Patna, 5. Registrar, Patna University, Patna, 6. Finance Officer, Patna University, Patna 7. Budget and Accounts Officer, Patna University, Patna, 8. Assistant Engineer(Elect.) Patna University, Patna, 9. Engineer Assistant, Works Department, Patna University, Patna, 10. Secretary to the Vice Chancellor, Patna University, Patna, 11. Incharge, Patna University Computer Centre for upload quotation document in Patna University website(www.patnauniversity.ac.in). The approval of same has been taken on concern file. 12. Mr. Manoj Kumar Mahto, Draftsman Gr-2 and Mr. Satyendra Kumar, UDC of Works Department, Patna University, Patna

Sd/-
University Engineer
Patna University, Patna

भ्रष्टाचारी के दबाव में मत रहें, निगरानी विभाग से मिलकर कहें

BID DOCUMENT

Cost of quotation document		
DD No.	Date	Amount
For Part-1:		₹ 2,500/-
For Part-2:		₹ 2,500/-
EMD 5% of Bid Amount		
DD No.	Date	Amount
For Part-1:		₹
For Part-2:		₹
Registration no. (If registered with MSME):		

Bid should indicate following information along with the self-attested photocopies of supporting documents:

1. THE FIRM
 - a) Name _____
 - b) Registration No of firm. _____
 - c) Address of Office at Patna _____
 - d) Contact Person's
 - i) Name & Design. _____
 - ii) Address _____
 - iii) Tel No. Landline _____ Mobile _____
 - iv) Email ID _____
2. Registration certificate of interior decorator architect:
3. Type of Firm : Proprietorship/ Private Ltd./Public Ltd./ Cooperative/ NGO/PSU (Please tick and enclose copy of Memorandum/ Articles of Association/ Certificate of Incorporation)

_____ enclosed. (Pl. specify)
4. PAN : _____ enclosed. (Pl. specify)
5. GST : _____ enclosed. (Pl. specify)
6. 3 years return file: FY 2018-19- Gross Value _____ Tax Deducted _____
 FY 2017-18 Gross Value _____ Tax Deducted _____
 FY 2016-17 Gross Value _____ Tax Deducted _____
7. Experience certificate of similar work: Value: ₹ _____ completion of year: _____.
 Name of Govt. Org./University: _____

Signatures of authorized person

Name _____

Designation _____

Seal

PRICE BID**Part-(1) Interior decoration work of Vice Chancellor Chamber, Patna University, Patna
(Civil and Electrical work)**

SL.NO.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	(A) CIVIL WORK				
1.01	Dismantling and rubbish cleaning	L.S	1		
1.02	Providing & making 5" brick wall	Sq.ft.	110		
1.03	Providing & applying plaster with sand and cement in the ratio 1:4	Sq.ft.	220		
			Total 'A'		
	(B) VC CHAMBER				
1.00	WALL FINISHES				
1.01	POP PATA PUNNING				
	Providing and applying plaster of pata paris with minimum thickness of 10mm to all wall surfaces in true level and plumb complete as directed	Sq.ft.	600		
1.02	EMULSION / ENAMEL PAINT				
	Providing and applying three coats of paints over two coat of primer to all wall and ceiling surfaces at all heights & levels with approved shade and texture. Surfaces to be prepared by scraping away all loose particles and then after Applying putty. Surfaces are then sand papered to achieve a smooth finish. Paint including cost of material, labour, scaffolding etc. all complete as directed by the engineer in charge.	Sq.ft.	850		
2.0	ELECTRICAL WORK				
	Providing and laying for internal electrification, circuit design with PVC insulated FRLS grade wires, FR grade flexible cable and FRLS grade PVC conduit, aluminum rac-way for under floor cable management for data, voice and table UPS and raw power circuit, sub main line, Ac line wiring, MCBs, DBs, Switch Socket Cable tray etc. as per drawings and specifications etc. Havels/Fenolex/ R.R / Equivalent make cables to be used. Norisis /Havels/ Crabtre /Equivalent make switches to be used.				
2.01	6 Amp Power Point	Nos.	16		
2.02	16 Amp Power Point	Nos.	2		
2.03	Main line with 10 mm wire	Mts.	15		
2.04	16 way Distribution box	Nos.	1		
2.05	12 watt led light	Nos.	13		
2.06	18 watt led light	Nos.	10		
2.07	Light point wiring 1.5 mm x 2 wire with pipe and switch	Mts.	45		
2.08	Celing Fan wiring with switch and regulatar	Nos.	2		
2.09	Fan point wiring 1x2mm wire with pipe and switch	Nos.	2		
2.10	2.5x2 mm/1.5x1 mm wiring for light and power line wiring	Mts.	10		

2.11	4x2mm/ 1.5x1mm wiring for AC power line wiring	Mts.	35		
2.12	AC Starter and socket	Nos.	2		
2.13	Voice and data with CAT-6 wire	Mts.	35		
2.14	Supply of Celing Fan	Nos.	1		
2.15	Supply of 2.4MP Dome camara	Nos.	2		
2.16	Supply of DVR 16 channel with SATA port & SATA	Nos.	1		
2.17	Supply of 4TB Sata hard disk as per specification	Nos.	1		
2.18	BNC and DC connectors	Nos.	6		
2.19	Supply of 16 channel SMPS	Nos.	1		
2.20	Vision-3 coaxial cable(1coil-90mts)	Nos.	3		
2.21	PVC boxes for mounting camaras	Nos.	2		
2.22	CCTV rack and LED Monitor	Nos.	1		
2.23	Other peripherals charges	Lot.	1		
				Total 'B'	
(C) VC REST ROOM					
1.00	WALL FINISHES				
1.01	EMULSION / ENAMEL PAINT				
	Providing and applying three coats of paints over two coat of primer to all wall and ceiling surfaces at all heights & levels with approved shade and texture. Surfaces to be prepared by scraping away all loose particles and then after Appling putty. Surfaces are then sand papered to achieve a smooth finish. Paint including cost of material, labour, scaffolding etc. all complete as directed by the engineer in charge.	Sq.ft.			
2.0	ELECTRICAL WORK				
	Providing and laying for internal electrification, circuit design with PVC insulated FRLS grade wires, FR grade flexible cable and FRLS grade PVC conduit, aluminum rac-way for under floor cable management for data, voice and table UPS and raw power circuit, sub main line, Ac line wiring, MCBs, DBs, Switch Socket Cable tray etc. as per drawings and specifications etc. Havels/Fenolex/ R.R / Equivalent make cables to be used. Norisis /Havels/ Crabtre /Equivalent make switches to be used.				
2.01	6 Amp Power Point	Nos.			
2.02	16 Amp Power Point	Nos.			
2.03	Main line with 10 mm wire	Mts.			
2.04	12 watt LED light	Nos.			
2.05	18 watt LED light	Nos.			
2.06	Light point wiring 1.5 mm x 2 wire with pipe and switch	Mts.			
2.07	Celing Fan wiring with switch and regulatar	Nos.			
2.08	Fan point wiring 1x2mm wire with pipe and switch	Nos.			
2.09	2.5x2 mm/1.5x1 mm wiring for light and power line wiring	Mts.			
2.10	4x2mm/ 1.5x1mm wiring for AC power line wiring	Mts.			
2.11	AC Starter and socket	Nos.			

2.12	Voice and data with CAT-6 wire	Mts.			
2.13	Supply of Celing Fan	Nos.			
2.14	Supply of 2.4MP Dome camara	Nos.			
2.15	Pvc boxes for mounting camaras	Nos.			
				Total 'C'	
(D) ATTACHED TOILET WITH VC ROOM					
1.00	TOILET				
1.01	Toilet to be made as per drawin and specifications. Jaguar make fittings and sanitary wares to be provided and fixed.	Nos.	1		
2.0	FLOORING & WALL CLADDING				
2.01	CERAMIC / VRITIFIED TILES				
	Providing & laying of tiles of approved make in pattern as per drawings and specifications on floor and wall up to 25mm thick bed of cement mortar, 1:4, giving necessary slopes, cleaning joints and grouting them in neat white cement / grout paste with pigmented additives to match shade of the tile. etc complete(tiles ranging up to Rs. 66/sft) rates for 1st floor, rupees 2 per sq.ft will be charged extra for lifting for each floor	Sq.ft.	192		
2.02	GRANITE				
	Providing & fixing of granite ranging upto 150/sft on wpc counter top including hold cutting and cut ours for sink as per detailed drawings on up to 25mm thick bed of cement mortar, 1:4, including surface preparation, applying neat cement float, giving necessary slopes, cleaning joints and grouting them in neat white cement paste with pigmented additives to match shade of granite. etc complete.	L.S	1		
2.03	POP PATA PUNNING				
	Providing and applying plaster of pata paris with minimum thickness of 10mm to all wall surfaces in true level and plumb complete as directed	Sq.ft.	132		
2.04	EMULSION / ENAMEL PAINT				
	Providing and applying three coats of paints over two coat of primer to all wall and ceiling surfaces at all heights & levels with approved shade and texture. Surfaces to be prepared by scraping away all loose particles and then after Appling putty. Surfaces are then sand papered to achieve a smooth finish. Paint including cost of material, labour, scaffolding etc. all complete as directed by the engineer in charge.	Sq.ft.	219		

3.0	ELECTRICAL WORK				
	Providing and laying for internal electrification, circuit design with PVC insulated FRLS grade wires, FR grade flexible cable and FRLS grade PVC conduit, aluminum rac-way for under floor cable management for data, voice and table UPS and raw power circuit, sub main line, Ac line wiring, MCBs, DBs, Switch Socket Cable tray etc. as per drawings and specifications etc. Havels/Fenolex/ R.R / Equivalent make cables to be used. Norisis /Havels/ Crabtre /Equivalent make switches to be used.				
3.01	6 Amp Power Point	Nos.	15		
3.02	16 Amp Power Point	Nos.	2		
3.03	Main line with 10 mm wire	Mts.	20		
3.04	12 watt LED light	Nos.	4		
3.05	18 watt LED light	Nos.	6		
3.06	Light point wiring 1.5 mm x 2 wire with pipe and switch	Mts.	30		
3.07	Fan point wiring 1x2mm wire with pipe and switch	Nos.	1		
3.08	2.5x2 mm/1.5x1 mm wiring for light and power line wiring	Mts.	30		
3.09	AC Starter and socket	Nos.	1		
				Total 'D'	
	(E) VC SECRETARY CHAMBER				
1.00	WALL FINISHES				
1.01	POP PATA PUNNING				
	Providing and applying plaster of pata paris with minimum thickness of 10mm to all wall surfaces in true level and plumb complete as directed	Sq.ft.	450		
1.02	EMULSION / ENAMEL PAINT				
	Providing and applying three coats of paints over two coat of primer to all wall and ceiling surfaces at all heights & levels with approved shade and texture. Surfaces to be prepared by scraping away all loose particles and then after Applying putty. Surfaces are then sand papered to achieve a smooth finish. Paint including cost of material, labour, scaffolding etc. all complete as directed by the engineer in charge.	Sq.ft.	600		
2.0	ELECTRICAL WORK				
	Providing and laying for internal electrification, circuit design with PVC insulated FRLS grade wires, FR grade flexible cable and FRLS grade PVC conduit, aluminum rac-way for under floor cable management for data, voice and table UPS and raw power circuit, sub main line, Ac line wiring, MCBs, DBs, Switch Socket Cable tray etc. as per drawings and specifications etc. Havels/Fenolex/ R.R / Equivalent make cables to be used. Norisis /Havels/ Crabtre /Equivalent make switches to be used.				

2.01	6 Amp Power Point	Nos.	10		
2.02	16 Amp Power Point	Nos.	1		
2.03	Main line with 10 mm wire	Mts.	20		
2.04	12 watt LED light	Nos.	10		
2.05	18 watt LED light	Nos.	9		
2.06	Light point wiring 1.5 mm x 2 wire with pipe and switch	Mts.	30		
2.07	Celing Fan wiring with switch and regulator	Nos.	2		
2.08	Fan point wiring 1x2mm wire with pipe and switch	Nos.	2		
2.09	2.5x2 mm/1.5x1 mm wiring for light and power line wiring	Mts.	30		
2.10	4x2mm/ 1.5x1mm wiring for AC power line wiring	Mts.	40		
2.11	AC Starter and socket	Nos.	2		
2.12	Voice and data with CAT-6 wire	Mts.	15		
2.13	Supply of Celing Fan	Nos.	1		
2.14	Supply of 2.4MP Dome camara	Nos.	2		
2.15	Supply of DVR 16 channel with SATA port & SATA	Nos.	2		
2.16	Supply of 4TB SATA hard disk as per specification	Nos.	1		
2.17	BNC and DC connectors	Nos.	6		
2.18	Supply of 16 channel SMPS	Nos.	1		
2.19	Vision-3 coaxial cable(1coil-90mts)	Nos.	3		
2.20	PVC boxes for mounting camaras	Nos.	2		
				Total 'E'	
	(F) MEETING ROOM				
1.00	WALL FINISHES				
1.01	POP PATA PUNNING				
	Providing and applying plaster of pata paris with minimum thickness of 10mm to all wall surfaces in true level and plumb complete as directed	Sq.ft.	700		
1.02	EMULSION / ENAMEL PAINT				
	Providing and applying three coats of paints over two coat of primer to all wall and ceiling surfaces at all heights & levels with approved shade and texture. Surfaces to be prepared by scraping away all loose particles and then after Applying putty. Surfaces are then sand papered to achieve a smooth finish. Paint including cost of material, labour, scaffolding etc. all complete as directed by the engineer in charge.	Sq.ft.	900		
2.0	ELECTRICAL WORK				
	Providing and laying for internal electrification, circuit design with PVC insulated FRLS grade wires, FR grade flexible cable and FRLS grade PVC conduit, aluminum rac-way for under floor cable management for data, voice and table UPS and raw power circuit, sub main line, Ac line wiring, MCBs, DBs, Switch Socket Cable tray etc. as per drawings and specifications etc. Havels/Fenolex/ R.R / Equivalent make cables to be used. Norisis /Havels/ Crabtre /Equivalent make switches to be used.				

5.01	6 Amp Power Point	Nos.	25		
5.02	16 Amp Power Point	Nos.	3		
5.03	Main line with 10 mm wire	Mts.	20		
5.05	12 watt led light	Nos.	16		
5.06	18 watt led light	Nos.	15		
5.07	Light point wiring 1.5 mm x 2 wire with pipe and switch	Mts.	30		
5.08	Celing Fan wiring with switch and regulatar	Nos.	3		
5.09	Fan point wiring 1x2mm wire with pipe and switch	Nos.	3		
5.10	2.5x2 mm/1.5x1 mm wiring for light and power line wiring	Mts.	20		
5.11	4x2mm/ 1.5x1mm wiring for AC power line wiring	Mts.	20		
5.12	AC Starter and socket	Nos.	1		
5.13	Voice and data with CAT-6 wire	Mts.	25		
5.14	Supply of Celing Fan	Nos.	2		
5.15	Supply of 2.4MP Dome camara	Nos.	2		
5.20	Vision-3 coaxial cable(1coil-90mts)	Nos.	3		
5.21	PVC boxes for mounting camaras	Nos.	2		
5.23	Other peripherals charges	Lot.	1		
				Total 'F'	
	(G) P.A ROOM				
1.00	WALL FINISHES				
1.01	POP PATA PUNNING				
	Providing and applying plaster of pata paris with minimum thickness of 10mm to all wall surfaces in true level and plumb complete as directed	Sq.ft.	400		
1.02	EMULSION / ENAMEL PAINT				
	Providing and applying three coats of paints over two coat of primer to all wall and ceiling surfaces at all heights & levels with approved shade and texture. Surfaces to be prepared by scraping away all loose particles and then after Applying putty. Surfaces are then sand papered to achieve a smooth finish. Paint including cost of material, labour, scaffolding etc. all complete as directed by the engineer in charge.	Sq.ft.	600		
				Total 'G'	
5.0	(H) ELECTRICAL WORK				
	Providing and laying for internal electrification, circuit design with PVC insulated FRLS grade wires, FR grade flexible cable and FRLS grade PVC conduit, aluminum rac-way for under floor cable management for data, voice and table UPS and raw power circuit, sub main line, Ac line wiring, MCBs, DBs, Switch Socket Cable tray etc. as per drawings and specifications etc. Havels/Fenolex/ R.R / Equivalent make cables to be used. Norisis /Havels/ Crabtre /Equivalent make switches to be used.				
5.01	6 Amp Power Point	Nos.	16		
5.02	16 Amp Power Point	Nos.	2		
5.03	Main line with 10 mm wire	Mts.	20		
5.04	12 watt LED light	Nos.	14		

5.05	18 watt LED light	Nos.	10		
5.06	Light point wiring 1.5 mm x 2 wire with pipe and switch	Mts.	25		
5.07	Celing Fan wiring with switch and regulatar	Nos.	1		
5.08	Fan point wiring 1x2mm wire with pipe and switch	Nos.	1		
5.09	2.5x2 mm/1.5x1 mm wiring for light and power line wiring	Mts.	15		
5.10	4x2mm/ 1.5x1mm wiring for AC power line wiring	Mts.	15		
5.11	AC Starter and socket	Nos.	1		
5.12	Voice and data with CAT-6 wire	Mts.	13		
5.13	Supply of Celing Fan	Nos.	1		
5.14	Supply of 2.4MP Dome camara	Nos.	2		
5.19	Vision-3 coaxial cable(1coil-90mts)	Nos.	1		
5.20	PVC boxes for mounting camaras	Nos.	2		
				Total 'H'	
(I) VIP WAITING AREA					
1.00	WALL FINISHES				
1.01	POP PATA PUNNING				
	Providing and applying plaster of pata paris with minimum thickness of 10mm to all wall surfaces in true level and plumb complete as directed	Sq.ft.	450		
1.02	EMULSION / ENAMEL PAINT				
	Providing and applying three coats of paints over two coat of primer to all wall and ceiling surfaces at all heights & levels with approved shade and texture. Surfaces to be prepared by scraping away all loose particles and then after Applying putty. Surfaces are then sand papered to achieve a smooth finish. Paint including cost of material, labour, scaffolding etc. all complete as directed by the engineer in charge.	Sq.ft.	550		
3.0	ELECTRICAL WORK				
	Providing and laying for internal electrification, circuit design with PVC insulated FRLS grade wires, FR grade flexible cable and FRLS grade PVC conduit, aluminum rac-way for under floor cable management for data, voice and table UPS and raw power circuit, sub main line, Ac line wiring, MCBs, DBs, Switch Socket Cable tray etc. as per drawings and specifications etc. Havels/Fenolex/ R.R / Equivalent make cables to be used. Norisis /Havels/ Crabtre /Equivalent make switches to be used.				
3.01	6 Amp Power Point	Nos.	15		
3.02	16 Amp Power Point	Nos.	2		
3.03	Main line with 10 mm wire	Mts.	20		
3.04	12 watt LED light	Nos.	15		
3.05	18 watt LED light	Nos.	12		
3.06	Light point wiring 1.5 mm x 2 wire with pipe and switch	Mts.	15		
3.07	Celing Fan wiring with switch and regulatar	Nos.	1		
3.08	Fan point wiring 1x2mm wire with pipe and switch	Nos.	1		
3.09	2.5x2 mm/1.5x1 mm wiring for light and	Mts.	20		

	power line wiring				
3.10	4x2mm/ 1.5x1mm wiring for AC power line wiring	Mts.	15		
3.11	AC Starter and socket	Nos.	1		
3.12	Voice and data with CAT-6 wire	Mts.	10		
3.13	Supply of Celing Fan	Nos.	1		
3.14	Supply of 2.4MP Dome camara	Nos.	2		
3.15	Vision-3 coaxial cable(1coil-90mts)	Nos.	1		
3.16	PVC boxes for mounting camaras	Nos.	2		
				Total 'I'	
(J) WAITING AREA					
1.01	POP PATA PUNNING				
	Providing and applying plaster of pata paris with minimum thickness of 10mm to all wall surfaces in true level and plumb complete as directed	Sq.ft.	550		
1.02	EMULSION / ENAMEL PAINT				
	Providing and applying three coats of paints over two coat of primer to all wall and ceiling surfaces at all heights & levels with approved shade and texture. Surfaces to be prepared by scraping away all loose particles and then after Appling putty. Surfaces are then sand papered to achieve a smooth finish. Paint including cost of material, labour, scaffolding etc. all complete as directed by the engineer in charge.	Sq.ft.	750		
5.0	ELECTRICAL WORK				
	Providing and laying for internal electrification, circuit design with PVC insulated FRLS grade wires, FR grade flexible cable and FRLS grade PVC conduit, aluminum rac-way for under floor cable management for data, voice and table UPS and raw power circuit, sub main line, Ac line wiring, MCBs, DBs, Switch Socket Cable tray etc. as per drawings and specifications etc. Havels/Fenolex/ R.R / Equivalent make cables to be used. Norisis /Havels/ Crabtre /Equivalent make switches to be used.				
5.01	6 Amp Power Point	Nos.	18		
5.02	16 Amp Power Point	Nos.	2		
5.03	Main line with 10 mm wire	Mts.	20		
5.04	12 watt LED light	Nos.	13		
5.05	18 watt LED light	Nos.	10		
5.06	Light point wiring 1.5 mm x 2 wire with pipe and switch	Mts.	35		
5.07	Celing Fan wiring with switch and regulatar	Nos.	2		
5.08	Fan point wiring 1x2mm wire with pipe and switch	Nos.	2		
5.09	2.5x2 mm/1.5x1 mm wiring for light and power line wiring	Mts.	15		
5.10	4x2mm/ 1.5x1mm wiring for AC power line wiring	Mts.	20		
5.12	Voice and data with CAT-6 wire	Mts.	10		
5.13	Supply of Celing Fan	Nos.	2		
5.14	Supply of 2.4MP Dome camara	Nos.	2		
5.15	Vision-3 coaxial cable(1coil-90mts)	Nos.	1		
5.16	PVC boxes for mounting camaras	Nos.	2		

			Total 'J'		
	(K) PANTRY				
1.00	Toilet to be made as per drawing and specifications. Jaguar make fittings and sanitary wares to be provided and fixed.	Nos.	1		
2.0	FLOORING & WALL CLADDING				
2.01	CERAMIC / VRTIFIED TILES				
	Providing & laying of tiles of approved make in pattern as per drawings and specifications on floor and wall up to 25mm thick bed of cement mortar, 1:4, giving necessary slopes, cleaning joints and grouting them in neat white cement / grout paste with pigmented additives to match shade of the tile. etc complete(tiles ranging up to Rs. 66/sft) rates for 1st floor, rupees 2 per sq.ft will be charged extra for lifting for each floor	Sq.ft.	308		
2.02	GRANITE				
	Providing & fixing of granite ranging upto 150/sft on wpc counter top including hold cutting and cut ours for sink as per detailed drawings on up to 25mm thick bed of cement mortar, 1:4, including surface preparation, applying neat cement float, giving necessary slopes, cleaning joints and grouting them in neat white cement paste with pigmented additives to match shade of granite. etc complete.	Sq.ft.	28		
2.03	POP PATA PUNNING				
	Providing and applying plaster of pata paris with minimum thickness of 10mm to all wall surfaces in true level and plumb complete as directed	Sq.ft.	72		
2.04	EMULSION / ENAMEL PAINT				
	Providing and applying three coats of paints over two coat of primer to all wall and ceiling surfaces at all heights & levels with approved shade and texture. Surfaces to be prepared by scraping away all loose particles and then after Applying putty. Surfaces are then sand papered to achieve a smooth finish. Paint including cost of material, labour, scaffolding etc. all complete as directed by the engineer in charge.	Sq.ft.	103		
3.0	ELECTRICAL WORK				
	Providing and laying for internal electrification, circuit design with PVC insulated FRLS grade wires, FR grade flexible cable and FRLS grade PVC conduit, aluminum rac-way for under floor cable management for data, voice and table UPS and raw power circuit, sub main line, Ac line wiring, MCBs, DBs, Switch Socket Cable tray etc. as per drawings and specifications etc. Havels/Fenolex/ R.R / Equivalent make cables to be used. Norisis /Havels/ Crabtre /Equivalent make switches to be used.				

3.01	6 Amp Power Point	Nos.	15		
3.02	16 Amp Power Point	Nos.	2		
3.03	Main line with 10 mm wire	Mts.	25		
3.04	12 watt LED light	Nos.	4		
3.05	18 watt LED light	Nos.	6		
3.06	Light point wiring 1.5 mm x 2 wire with pipe and switch	Mts.	30		
3.07	Fan point wiring 1x2mm wire with pipe and switch	Nos.	1		
3.08	2.5x2 mm/1.5x1 mm wiring for light and power line wiring	Mts.	20		
3.09	Supply of 2.4MP Dome camara	Nos.	1		
3.10	PVC boxes for mounting camaras	Nos.	1		
				Total 'K'	
(L) TOILET					
1.00	Toilet to be made as per drawin and specifications. Jaguar make fittings and sanitary wares to be provided and fixed.	Nos.	1		
2.0	FLOORING & WALL CLADDING				
2.01	CERAMIC / VRITIFIED TILES				
	Providing & laying of tiles of approved make in pattern as per drawings and specifications on floor and wall up to 25mm thick bed of cement mortar, 1:4, giving necessary slopes, cleaning joints and grouting them in neat white cement / grout paste with pigmented additives to match shade of the tile. etc complete(tiles ranging up to Rs. 66/sft) rates for 1st floor, rupees 2 per sq.ft will be charged extra for lifting for each floor	Sq.ft.	160		
2.02	GRANITE				
	Providing & fixing of granite ranging upto 150/sft on wpc counter top including hold cutting and cut ours for sink as per detailed drawings on up to 25mm thick bed of cement mortar, 1:4, including surface preparation, applying neat cement float, giving necessary slopes, cleaning joints and grouting them in neat white cement paste with pigmented additives to match shade of granite. etc complete.	L.S	1		
2.03	POP PATA PUNNING				
	Providing and applying plaster of pata paris with minimum thickness of 10mm to all wall surfaces in true level and plumb complete as directed	Sq.ft.	72		
2.04	EMULSION / ENAMEL PAINT				
	Providing and applying three coats of paints over two coat of primer to all wall and ceiling surfaces at all heights & levels with approved shade and texture. Surfaces to be prepared by scraping away all loose particles and then after Appling putty. Surfaces are then sand papered to achieve a smooth finish. Paint including cost of material, labour, scaffolding etc. all complete as directed by the engineer in charge.	Sq.ft.	103		

3.0	ELECTRICAL WORK				
	Providing and laying for internal electrification, circuit design with PVC insulated FRLS grade wires, FR grade flexible cable and FRLS grade PVC conduit, aluminum rac-way for under floor cable management for data, voice and table UPS and raw power circuit, sub main line, Ac line wiring, MCBs, DBs, Switch Socket Cable tray etc. as per drawings and specifications etc. Havels/Fenolex/ R.R / Equivalent make cables to be used. Norisis /Havels/ Crabtre /Equivalent make switches to be used.				
3.01	6 Amp Power Point	Nos.	15		
3.02	16 Amp Power Point	Nos.	2		
3.03	Main line with 10 mm wire	Mts.	15		
3.04	12 watt LED light	Nos.	4		
3.05	18 watt LED light	Nos.	6		
3.06	Light point wiring 1.5 mm x 2 wire with pipe and switch	Mts.	25		
3.07	Fan point wiring 1x2mm wire with pipe and switch	Nos.	1		
3.08	2.5x2 mm/1.5x1 mm wiring for light and power line wiring	Mts.	20		
				Total 'L'	
Gross Total of Part- 1(A to L)-					₹

Special Terms & Conditions :

- 1 Work to be completed with in 25 working days from the date of work order.
- 2 Work schedule can be followed uninterrupted if the payment schedules are maintained.
- 3 Taxes inclusive as applicable according to the government of India prevailing rates.
- 4 Billing will be done according to final measurement and quantity counts.
- 5 Rates are valid for 30 days from the date of submission of quotation.
- 6 24-hour water and electricity to be provided free of cost at working site with power back up.
- 7 Labour wasted for reason of electricity or any local hazards agency will have to bear the cost as actual.
Any hazard by the police or local will have to be handled by the agency and agency will have to bear the expenses as actual.
- 8 Safe storage space to be provided by the P.U free of cost for keeping construction materials.
- 9 Century sainink, Alishan or equivalent make MR ply / block board to be used.
- 10 Godrej or Hafele or equivalent make hardware to be provided and fixed.
- 11 Extra work will be charged as per market prevailing rates.

Place.....

Signatures of authorize

Date.....

Name_____

Seal:

Annexure-2**PRICE BID****Part-2 Interior decoration work of Vice Chancellor Chamber, Patna University, Patna
(Flooring and Furniture Work)**

SL.NO	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
(A) VC CHAMBER					
1.00	V.C. TABLE				
	Structure to be made out off M.S finished with N.C paint of approved shade and spactions. Table top to be made out of marble ranging up to Rs. 400/sft. Marble to be mirror polished finished as per design and specifications.	Nos.	1		
2.00	BACK ANNEXE/CABINET				
	Structure to be made out off ply/block board as and where required Veneer ranging up to Rs.100/sft to be provided and fixed. Finished with mat malamine coating. Necessary hardware of Godrej, Halefe or equivalent make to be provided and fixed (Total value hardwares will be within Rs. 3000) as and where necessary.	Sq.ft.	77		
3.00	WALL PANELLING				
	Providing & fixing POP moulding for wall paneling as per design and specification .	Rft	700		
4.00	SOFA				
	Structure to be made out of hard wood. 4" high density foam and other required materials to be used for making the sofa and finished with tapestry ranging upto 1000/- per meter				
4.01	2 seater sofa	Nos.	2		
4.02	1 seater sofa	Nos.	1		
				Total 'A'	
(B) WARDROBE					
1.01	Structure to be made out off mr ply/block board as and where required laminate ranging upto Rs. 1800/sheet to be provided and fixed. Necessary hardware of Godrej, Halefe or equivalent make to be provided and fixed (Total value hardwares will be within Rs. Rs.3000) as and where necessary.	Sq.ft.	27		
1.02	SINGLE BED				
	Structure to be made out off mr ply/block board as and where required laminate ranging up to Rs. 1800/sheet to be provided and fixed. Necessary hardware of Godrej, Halefe or equivalent make to be provided and fixed (Total value hardwares will be within Rs. Rs.1000) as and where necessary.	Nos.	1		
1.03	SIDE TABLE				
	Providing & fixing bed side table as per design and specification (Total value hardwares will be within Rs. Rs.1000)	Nos.	1		
				Total 'B'	
(B) ATTACHED TOILET WITH VC ROOM					
1.00	CABINET				
	Structure to be made out off mr ply/block board as and where required laminate ranging up to	Sq.ft.	6		

	Rs. 1800/sheet to be provided and fixed. Necessary hardware of Godrej, Halefe or equivalent make to be provided and fixed (Total value hardwares will be within Rs.1200) as and where necessary.				
				Total 'C'	
(D) VC SECRETARY CHAMBER					
1.00 SECRETARY TABLE					
	Structure to be made out off mr ply/block board as and where required laminate ranging up to Rs. 1800/sheet to be provided and fixed . Necessary hardware of Godrej, Halefe or equivalent make to be provided and fixed (Total value hardwares will be within Rs.2500) as and where necessary.	Nos.	1		
2.00 CABINET					
	Structure to be made out off water proof ply/block board as and where required laminate ranging up to Rs. 1800/sheet to be provided and fixed. Necessary hardware of Godrej, Halefe or equivalent make to be provided and fixed (Total value hardwares will be within Rs..2500) as and where necessary.	sq. ft.	72		
3.00 BACK ANNEXE					
	Structure to be made out off water proof ply//block board as and where required Veneer ranging up to Rs. 100/sft to be provided and fixed and finished with mat malamine coating . Necessary hardware of Godrej, Halefe or equivalent make to be provided and fixed (Total value hardwares will be within Rs.3000) as and where necessary.	Sq.ft.	16		
4.00 SIDE ANNEXE					
	Structure to be made out off ply/block board as and where required laminate ranging up to Rs. 1800/sheet to be provided and fixed and finished with mat malamine coating. Necessary hardware of Godrej, Halefe or equivalent make to be provided and fixed (Ranging up to Rs.3000) as and where necessary.	Sq.ft.	6		
				Total 'D'	280660.00
(E) MEETING ROOM					
1.0 FLOORING					
1.01 WOODEN FLOORING					
	Providing & laying of laminated wooden flooring of approved make in pattern as per drawings and specifications of Pergo or equivalent make to be provided and fixed.	Sq.ft.	284		
2.00 CONFERENCE TABLE					
	Structure to be made out off water proof ply/block board as and where required laminate ranging up to Rs. 1800/sheet to be provided and fixed .Necessary hardware of Godrej, Halefe or equivalent make to be provided and fixed (Total value hardwares will be within Rs. Rs.5000) as and where necessary.	Nos.	1		
3.00 MULTIPURPOSE UNIT					

	Table Structure to be made out off ply/block board as and where required Veneer ranging up to Rs. 100/sft to be provided and fixed and finished with mat malamine coating. Necessary hardware of Godrej, Halefe or equivalent make to be provided and fixed (Total value hardwares will be within Rs. 4000) as and where necessary.	Sq.ft.	12		
4.00	WALL PANELLING				
	Providing & fixing POP moulding wall paneling as per design and specification .	Rft	520		
			Total 'E'		
(F) VIP WAITING					
1.00	LOOSE FURNITURE				
	Structure to be made out of hard wood. 4" high density foam and other required materials to be used for making the sofa and finished with tapestry ranging upto 1000/- per meter				
1.01	3 seater sofa	Nos.	3		
1.02	1 seater sofa	Nos.	1		
			Total 'F'		
(G) P.A CHAMBER					
1.00	FURNITURES				
	Structure to be made out off mr ply/block board as and where required laminate ranging up to Rs. 1800/sheet to be provided and fixed .Necessary hardware of Godrej, Halefe or equivalent make to be provided and fixed (Total value hardwares will be within Rs..2500) as and where necessary.				
1.01	P.A table	Nos.	1		
2.00	SIDE ANNEXE				
	Structure to be made out off ply/block board as and where required laminate ranging up to Rs. 1800/sheet to be provided and fixed and finished with mat malamine coating. Necessary hardware of Godrej, Halefe or equivalent make to be provided and fixed (Total value hardwares will be within Rs.2000) as and where necessary.	Sq.ft.	9		
			TOTAL 'G'		
(H) DOOR & DOOR FRAME PANELING					
7.08	Providing & fixing panelling on frame with Ply of appropriate thickness finished with Laminate/Veneer as per design and specification.	Sq.ft.	196		
			Total 'H'		
Gross Total of Part-2(A to G) ₹					

Special Terms & Conditions :

- 1 Work to be completed with in 25 working days from the date of work order.
- 2 Work schedule can be followed uninterrupted if the payment schedules are maintained.
- 3 Taxes inclusive as applicable according to the government of India prevailing rates.
- 4 Billing will be done according to final measurement and quantity counts.
- 5 Rates are valid for 30 days from the date of submission of quotation.
- 6 24-hour water and electricity to be provided free of cost at working site with power back up.

- 7 Labour wasted for reason of electricity or any local hazards agency will have to bear the cost as actual.
Any hazard by the police or local will have to be handled by the agency and agency will have to bear the expenses as actual.
- 8 Safe storage space to be provided by the P.U free of cost for keeping construction materials.
- 9 Century sainink, Alishan or equivalent make MR ply / block board to be used.
- 10 Godrej or Hafele or equivalent make hardware to be provided and fixed.
- 11 Extra work will be charged as per market prevailing rates.
- 12 In the event of delay in completion of work after the stipulated period, the agency shall be liable to pay liquidated damages at a percentage of the total order value subject to minimum of Rs. 500.00 and maximum of 3% as detailed below:

(A) @ 1% for the first week

(B) @ 2% for the second week

(C) @ 3% for the third week & above

Place.....

Date.....

Signatures of authorize

Name _____

Seal: